



RWANDA TRANSPORT DEVELOPMENT AGENCY

P.O Box 6674

KG 563 St., Queen's Land House

Email: info@rtda.gov.rwKIGALI

Permanent Secretary

Ministry of Defence

KIGALI

Dear Sir,

RE: URGENT REPAIR WORKS OF DAMAGES OCCURRED ON KADUHA-BUHANDA- KIRENGERI ROAD IN RUHANGO AND NYAMAGABE DISTRICTS.

Request for quotations and invitation for negotiations


Reference is made to:

- i) The MoU between the Ministry of Defence, The Ministry of Infrastructure, The Ministry of Finance and Economic Planning and The Ministry of Local Government on partnership for use of Force Account in all government institutions signed on 25th April 2022;
- ii) The Quantities estimation signed jointly with RTDA and Engineer Command representative respectively on 08th to 10th June 2023

We would therefore like to invite RDF-Engineer Command to submit cost estimates for the anticipated works as per the attached bill of quantities. Immediate negotiations are to be done after submission of the bills of quantities to ensure urgent intervention.

Please accept, Permanent Secretary, the assurance of our highest consideration.

Sincerely,


Imena MUNYAMPENDA
Director General

Cc:

- Hon. Minister of Infrastructure
 - Hon. Minister of State / MININFRA
 - Permanent Secretary / MININFRA
 - Director General / RMF
 - Commander / RDF-Engineer Command
- KIGALI

HL&S

Handle urgently

Hou
28/06/23

cc

- Comd

Construction

BILL OF QUANTITY FOR URGENT REPAIR WORKS OF KADUHA-BUHANDA-KIRENGERI ROAD SLOPE FAILURES.

SPOT NO.	DESCRIPTION	Unit	QTY	UNIT PRICE	TOTAL AMOUNT
100	Site Instalation ,Topography and Geotechnical investigation				
101	Site installation	Ls	1		
102	Topographic survey before, during and after works	Ls	1		
103	Ruhondo River Deviation (50m)	ls	1		
104	Geotechnical investigation	Ls	1		
	Sub/Total 100				
200	Preliminary & Earthworks				
201	Repair of deck of bridge with wooden planks	ml	848		
202	Painting og bridge guardrail	ls	1		
203	Removal of identified landslides including the overhaul	m3	456		
204	Removal of weakned material from the lower side of the road	m3	1450		
205	Trenche exavation for culvert	m3	182		
	Sub Total/200				
300	Filling works				
301	Fill and compaction with selected material from the borrow pit(tout venant)	m3	1778		
302	Fill and compaction with murrum from the borrow pit	m3	256		
			1,1		
303	Overhaul transportation beyond 5km.	km/ m3	85,333		
	Sub Total/300				
400	Drainage and Protection system				
401	Stone rip rap (30 to 50kg)	m3	342		
402	Concrete for bed outflow ditch	m3	48		
403	Construction of ditch in stone masonry	m3	45		

6

404	Construction of manhole for culvert inlet and outlet in stone masonry	m3	88		
405	Construction of head wall in stone masonry	m3	1.4 4		
406	Outflow chanel in stone masonry on lower side outlet of the culvert	m3	186		
407	Suply and install culvert 100φ	pce	9		
408	Retaining wall in Gabions	m3	300		
409	Supply and install the geotextile	m2	350		
410	Grass planting for slope sabilization	m2	20. 8		
	Sub Total 400				
	TOTAL				
	WITHHOLDING TAX 15%				
	GRAND TOTAL INCLUDING TAX				

